

*If you are using a printed copy of this procedure, and not the on-screen version, then you **MUST** make sure the dates at the bottom of the printed copy and the on-screen version match.
The on-screen version of the Collider-Accelerator Department Procedure is the Official Version.
Hard copies of all signed, official, C-A Operating Procedures are kept on file in the C-A ESHQ Training Office, Bldg. 911A.*

C-A OPERATIONS PROCEDURES MANUAL

8.16.3 Operating the LINAC Transport Cooling System

Text pages 2 through 3

Hand Processed Changes

<u>HPC No.</u>	<u>Date</u>	<u>Page Nos.</u>	<u>Initials</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Approved: _____
Signature on File
Collider-Accelerator Department Chairman _____
Date _____

R. Grandinetti

8.16.3 Operating the LINAC Transport Cooling System

1. Purpose

To provide operating instruction to the Water Systems technicians for this operation of the LINAC transport cooling system.

2. Responsibilities

Water Systems technicians start and stop this system.

3. Prerequisites

3.1 Startup - Request permission from LINAC control.

3.2 Verify that chilled water system is operating.

3.3 Shutdown - Request permission from LINAC control.

3.4 Qualified and trained Water Systems technician.

4. Precautions

Do not operate pumps without water or with valves closed.

5. Procedure

5.1 Verify that water level is within operating limits as marked on the transport expansion tank sight glass.

5.2 Open suction and discharge valves on selected pump.

5.3 Roll pump shaft by hand.

5.4 Reduce set point on pressure controller to 25 - 50 psi.

5.5 Turn on transport circuit breaker.

5.6 Start pump at local start/stop station.

5.7 Increase set point on pressure controller to original value (120 psi).

5.8 Check system pressure (120 psi), flow (300 gpm), and temperature (75°F) for proper settings and operation.

- 5.9 Observe pump operation and restore alarms.
- 5.10 Check system resistivity (0.5 - 1 megohm).
- 5.11 For shutdown, reduce pressure control setting, turn off pump, close suction and discharge valves, and secure alarms.

6. Documentation

None

7. References

- 7.1 LINAC flow diagram, C.T. Main Drawing #2484-402-M3.

8. Attachments

None